Screening Site Inspection Final Report for

Rueben Murrell Site
ILD 984 769 240

February 23, 1993

B&V Waste Science and Technology Corp.
101 North Wacker Drive
Suite 1100
Chicago, Illinois 60606

Contents

Tables

Contents (Continued)

Figures

Appendices

1.0 Introduction

On August 7, 1991, B&V Waste Science and Technology Corp. was authorized by approval of the Work Plan by the U.S. Environmental Protection Agency (USEPA), Region V, to conduct a screening site inspection (SSI) of the Rueben Murrell site in Macon County, Illinois.

The site was initially placed on the Comprehensive Environmental Response, Compensation and Liability Act Information System (CERCLIS) on February 10, 1989 as a result of a request for discovery action initiated by the Illinois Environmental Protection Agency (IEPA).

The site received its initial Comprehensive Environmental Response, Compensation, and Liability Act (CERCLA) evaluation in the form of a Preliminary Assessment (PA) report completed by Karen Petefish of the IEPA on September 21, 1989. The sampling portion of the SSI was conducted on January 8, 1992, when the sampling team collected four soil samples.

The purposes of the SSI have been stated by the USEPA in a directive outlining pre-remedial program strategies. Essentially, the directive states:

> All sites will receive a screening SI to 1) collect additional data beyond the PA to enable a more refined preliminary HRS (Hazard Ranking System) score; 2) to establish priorities among sites most likely to qualify for the NPL (National Priorities List); and 3) to identify the most critical data requirements for the listing [expanded] SI step. A Screening SI will not have rigorous data quality objectives (DQOs). Based on the refined preliminary HRS score and other technical judgement factors, the site will then either be designated as NFRAP (no further remedial action planned) [currently designated SEA (site evaluation accomplished)] or carried forward as an NPL candidate. A listing [expanded] SI will not automatically be done on these sites. First, they will go through a management evaluation to determine whether they can be addressed by another authority such as RCRA (Resource Conservation and Recovery Act) ... Sites that are designated as NFRAP [SEA] or deferred to other statutes are not candidates for a listing [expanded] SI.
>
> The listing [expanded] SI will address all the data requirements of the revised HRS using field screening and NPL level DQOs. It may also provide needed data in a format to support remedial investigation work plan development.

> Only sites that appear to score high enough for listing and that have not been deferred to another authority will receive a listing [expanded] SI (USEPA, 1988).

USEPA Region V requested B & V Waste Science and Technology Corp. to identify sites during the SSI that may require removal action to remediate an immediate human and/or environmental threat.

2.0 CERCLA Site Description

2.1 Introduction

This section includes information obtained during the SSI and from reports of previous activities involving this site.

2.2 Site Description

The Rueben Murrell site is on Hill Road southwest of Decatur, Illinois. The 17 acre site lies in the northeast quarter of Section 23, Township 16 North, Range 1 East in the Third Principal Meridian, Macon County, Illinois. Figure 2-1 is a Site Location Map and Figure 2-2 is a Site Sketch.

The Rueben Murrell site is in a rural area outside of Decatur, Illinois. Decatur has a population of 84,000 (U.S. Department of Commerce, 1991). The property is bordered on the east and west by residential homes, on the south by Hill Road and more residences, and on the north by farmland. Access to the site is gained by a driveway off of Hill Road. A barbed wire fence in poor condition surrounds most of the site. The city of Decatur is about five miles east of the site.

Site topography is generally flat except for the southern part of the property, which slopes down toward Hill Road. Surface water runoff is towards the Sangamon River, which is 900 feet south of the site.

Two buildings are on the site: the Murrell residence and a three car garage. Oil stains were observed on the driveway and nearby soils. Oil stains were the heaviest in front of the garage. Scrap metal, vehicle parts, and old tires were among the items littering the driveway. North of the buildings is a horse pasture surrounded by a fence. Two trash piles with pallets, scrap metal, tires, empty drums, and other items are inside the fence.



SOURCE: USGS Topographic Map, 1982 Harristown Quadrangle	N	Figure 2–1 Site Location Map
SCALE: 1:24,000		Rueben Murrell Decatur, Illinois

B&V Waste Science and Technology Corp.


HORSE PASTURE
GARBAGE PILES
FISH POND
BARBED WIRE FENCING
GATE
OTHER RESIDENCES
MURRELL RESIDENCE
3 CAR GARAGE
OIL RESIDUE AREA
WELL
OTHER RESIDENCES
TO TWIN LAKES RD.
HILL ROAD
TO JOYNT ROAD
SANGAMON RIVER (APPROXIMATELY 900')
Not to Scale
N
Figure 2-2
Site Sketch
Rueben Murrell
Decatur, Illinois
B&V Waste Science and Technology Corp.

2.3 Site History

2.3.1 Operational History

Rueben Murrell purchased the site from Arnold Murrell, his brother. Before its use as a private residence, the site was probably undeveloped.

The site is used as a private residence. Complaints filed at the Macon County Health Department allege the Murrells allow trash dumping on their property. There is no record of the disposition of the complaints as the court records were dismissed and destroyed on May 4, 1984 (Decatur, States Attorney Office, 1993). There are no violations currently pending against the Rueben Murrell site (Macon County Health Department, 1993). Two trash piles, of unknown source, were observed north of the residence.

2.3.2 Summary of Onsite Environmental Work

Other than the IEPA Preliminary Assessment, there is no evidence of any environmental work on the property, past or present.

2.4 Applicability of Other Statutes

Rueben Murrell is listed in the CERCLIS site listing for Illinois (USEPA, 1992a). The site is not listed as a RCRA notifier in Illinois (USEPA, 1992b).

3.0 Site Inspection Activities and Analytical Results

3.1 Introduction

This section outlines procedures utilized and observations made during the SSI conducted at the Rueben Murrell site. Sampling activities were in accordance with the Quality Assurance Project Plan (QAPjP), dated September 27, 1991.

Appendix B presents the USEPA Potential Hazardous Waste Site Inspection Report (Form 2070-13).

Samples collected for this SSI were analyzed for organic and inorganic substances contained on the USEPA Target Compound List (TCL) and Target Analyte List (TAL), by USEPA contract laboratory program (CLP) participant laboratories. Appendix C presents the TCL and TAL. Appendix D presents a summary of all analytical data generated by SSI sampling is presented in Appendix D of this report. Appendix E contains photographs of the site and sample locations.

3.2 Site Reconnaissance

On September 18, 1991, a site reconnaissance of the Rueben Murrell site was conducted. This visit included a visual inspection of the site to determine the site status, delineate facility activities, identify potential sampling locations, and to determine any health or safety hazards.

3.3 Site Representative Interview

Mr. Rueben Murrell and his son, Mr. Rueben Murrell Jr. were interviewed by the reconnaissance team on September 18, 1991 at the Rueben Murrell site in Decatur, Illinois. The reconnaissance team discussed the purpose of the SSI with the Murrells, and gathered site specific information. The Murrells stated that the IEPA had not visited their residence, only the landfill on a hill southeast of the residence. The reconnaissance team informed the Murrells that this screening site inspection is concerned with the residence of Mr. Rueben Murrell.

3.4 Soil Sampling

On January 8, 1992, a field team collected four soil samples. Figure 3-1 shows the location of each sample, Table 3-1 provides sample locations and descriptions.

Soil samples were collected with clean, stainless steel spoons. Samples were placed in sample jars provided by USEPA CLP participant laboratories. Rueben Murrell did not split samples collected by the field team.

Table 3-1
Sample Summary

Sample #	Matrix	Depth	Appearance	Location
SS01	Surface Soil	0-6 inches	Medium brown color	Front yard of the Murrell residence. Sample was taken south of the residence.
SS02	Surface Soil	0-6 inches	Dark in color, oily	Southeast corner, in front of the garage located at southeast corner of the site.
SS03	Surface Soil	0-6 inches	Thin layer of topsoil, light brown clay beneath	North trash pile. Sample taken along east side of trash pile.
SS04	Surface Soil	0-6 inches	Medium brown color	South trash pile. Sample taken along east side of trash pile.

Sample jars were labeled, packaged, sealed, and transported to USEPA CLP participant laboratories in accordance with procedures set forth in the September 27, 1991 QAPjP. Soil samples scheduled for organic analysis were shipped to Wadsworth/Alert Laboratories, Inc. in North Canton, Ohio, on January 8, 1992. Soil samples scheduled for inorganic analysis were shipped to IT Analytical Services-



Not to Scale	N	FIGURE 3–1 Sample Location Map Rueben Murrell Decatur, Illinois

B&V Waste Science and Technology Corp.

Export in Export, Pennsylvania on January 8, 1992. Samples were analyzed for TCL and TAL substances under a routine analytical services request.

All reusable sampling and personal protective equipment (PPE) were decontaminated before transport offsite. Disposable sampling and PPE items were discarded in accordance with procedures outlined in the SSI project work plan and QAPjP.

A background sample, SS01, was collected in the front yard of the Rueben Murrell residence. This location was selected as representative of natural soil conditions in the area. Sample SS02 was taken from near the southeastern corner of the cinderblock, three-car garage, where the soil is stained and is oily in appearance. Samples SS03 and SS04 were taken from the two garbage piles in the Murrell's backyard. Sample SS04 came from the garbage pile which is located closest to the Murrell residence.

3.5 Analytical Results

This section summarizes analytical results from samples collected during the SSI. Appendix D presents all analytical data generated and tabulated in this SSI.

Volatiles were not detected in any of the surface soil samples. Sample SS02 is the surface soil taken from an area covered with an oily residue near the southeast corner of the Murrell's garage. This sample contained eight semivolatile compounds, including phthalates, polyaromatic hydrocarbons, and a phenol; three inorganic substances, one pesticide, and two congeners of PCB's. Samples SS03 and SS04 are surface soil taken from the east side of the two trash piles in the Murrell pasture. The sample from the northern most pile (SS03) contains one semivolatile compound, two isomers of a pesticide, one congener of PCB, and one inorganic substance. The sample from the southern most pile (SS04) contains three inorganic substances and one congener of PCB.

3.6 Key Samples

Key samples are those samples that contain substances in sufficient concentration to document an observed release. Table 3-2 identifies key samples taken during the SSI that meet these criteria as analytically significant.

Table 3-2
Key Sample Summary

Analysis	Sample Location and Number			Background
Semi-volatile Compounds (ug/kg)	SS02	SS03	SS04	SS01
Butylbenzylphthalate	1100 J			460 U
Chrysene	650 J			460 U
Fluoranthene	1400 J			460 U
4-Methylphenol	1700 J			460 U
2-Methylnaphthalene	710 J			460 U
bis(2-Ethylhexyl)phthalate	4800 J			460 UJ
Benzo(b)Fluoranthene	610 J			460 U
Naphthalene		530		460 U
Phenanthrene	1400 J			460 U
Pyrene	1200 J			460 UR
Pesticides/PCBs (ug/kg)				
Alpha-Chlordane		5.9 JP		2.4 UJ
Gamma-Chlordane		11 JP		2.4 UJ
Endrin	10 JP			4.6 UJ
Aroclor-1242		510 JP		46 UJ
Aroclor-1248	810 J			460 J
Aroclor-1254	350 J		150 P	46 UJ
Metals (mg/kg)				
Beryllium	0.77 B			0.28 U
Cadmium	2.0		1.6 B	0.42 B
Cyanide		0.66 B	0.49 B	0.28 U
Lead	126		173	32

U - Indicates compound was analyzed for but not detected.
P - Indicates a greater than 25% difference for detected concentrations between two GC columns. The lower of the two values was reported.
J - Indicates an estimated value.
B - Indicates the analyte is found in the associated blank.
R - Indicates the sample results are rejected because quality control criteria were not met.

4.0 Characterization of Sources

4.1 Introduction

Analysis of samples collected during the SSI has led to the identification of one source pathway at the Rueben Murrell site: soil. The other pathways (groundwater, surface water, and air) were not sampled and there is no evidence to support another source.

4.2 Contaminated Soil

4.2.1 Description

Based on the analytical results of soil samples SS01-SS04 collected during the SSI sampling event, approximately one-and-one-half acres of soil are considered to contain chemicals of concern. This area includes the two garbage piles estimated at one-half acre a piece and the area (one-half acre) in front of the cinderblock garage. The total area of concern is defined by the location of key samples (SS01-SS04).

4.2.2 Waste Characteristics

SSI analytical results indicate the area of affected soil is contaminated with 11 semi-volatile compounds, six pesticide/PCBs, 3 metals, and cyanide. These chemicals, along with their respective concentrations are listed in Table 3-2.

4.2.3 Potentially Affected Migration Pathways

The chemicals of concern associated with the site appear to be affecting the soil pathway and could potentially affect the other three pathways. Groundwater could become affected by chemicals leaching through the soil, and the air pathway is of concern due to the possible distribution of chemicals in the form of windblown particulate matter.

4.3 Other Potential Sources Within 1 Mile

Three landfills may be within 1 mile of the site. Two of these landfills, whose locations were not verified, the Macon #2 and the Macon County Landfill are on the CERCLIS listing (USEPA, 1992a). The third is the unpermitted Murrell Landfill less than a half mile southeast of the site.

5.0 Discussion of Migration Pathways

5.1 Introduction

This section includes information useful to analyze the potential impact of contaminants found at the Rueben Murrell site, on the four migration pathways (groundwater, surface water, air and soil).

5.2 Groundwater

No groundwater samples were collected during the SSI sampling trip. Site-specific information on the geology of the Rueben Murrell site is not available.

The regional geology around the Rueben Murrell site is comprised of undifferentiated glacial drift units over sedimentary bedrock formations. A detailed statewide study by Berg and Kempton (1988) provides three-dimensional mapping of geological materials to a depth of 50 feet. Near the site, their map suggests the overburden is composed, in descending order, of the following sediments: less than 20 feet of loess, greater than 20 feet of loamy and sandy till, over discontinuous silty and clay till.

The subcropping bedrock is expected to be Pennsylvanian shale with the sandstone, limestone, and coal beds (Selkregg and Kempton, 1958). The Pennsylvanian bedrock can only produce small quantities of groundwater.

Well data from the Illinois State Water Survey (ISWS, 1992) indicates all rural residents within the 4 mile target distance are supplied by groundwater drawn from the glacial drift. Figure 5-1 shows the location of the nearest occupied residence and private well. Table 5-1 presents the population using private wells within 4 miles of the site. Approximate population values presented in Table 5-1 were determined by multiplying the Macon County average of 2.35 persons per household (U.S. Department of Commerce, 1991) by the number of houses counted in each distance ring on a topographic map (U.S. Geological Survey, 1982).



Figure 5–1
Location of Nearest Residence

Rueben Murrell
Decatur, Illinois

B&V Waste Science and Technology Corp.

Table 5-1 Private Well Users	
Radial Distance From Rueben Murrell In Miles	Approximate Population Served By Private Wells
0.00 - 0.25	65
0.25 - 0.50	42
0.50 - 1.00	117
1.00 - 2.00	314
2.00 - 3.00	169
3.00 - 4.00	286
Total Population	993

Source: U.S. Geological Survey, 1982

5.3 Surface Water

The Rueben Murrell site is fairly flat. Runoff from precipitation generally drains south of the site to Hill Road and toward the Sangamon River. The Sangamon River flows to the southwest at approximately six hundred eighty cubic feet per second (IEPA, 1990). The probable point of entry to the Sangamon River is about nine hundred feet south of the site. No surface water intakes are within 15 miles downstream of the site. The city of Decatur uses surface water from the Sangamon River for its public water supply; however, the closest city water intake is approximately four miles upstream from the site. Table 5-2 presents information on this intake. No critical habitats for endangered species are known on the Sangamon River, within 15 miles downstream from the site (Illinois Department of Conservation, 1992). The Sangamon River appears to be used only for recreational purposes.

Table 5-2
Public Water Supply Sources Within 4 Miles of Rueben Murrell

Distance/Direction From Site	Source Name	Location of Source	Population Served	Source Type
4 miles northeast	Decatur municipal water	Lake Decatur	31,063	Surface Water

Source: City of Decatur, 1992

No records of endangered or threatened species were found within a 4-mile radius of the Rueben Murrell site (Illinois Department of Conservation, 1992). The Lincoln Trail Homestead State Park is within 3 miles of the site (USGS, 1982).

5.4 Air

The Rueben Murrell site contains garbage piles, construction waste, miscellaneous automobile parts, and areas of oily waste. These areas are not contained and are therefore open to the air. During the screening site inspection, the odor of garbage was noted coming from the pasture. The presence of chemicals of concern at or near the ground surface creates the potential for windblown particulate matter, which could be an inhalation hazard to the Murrells and neighboring residences. There are approximately twenty-seven houses within a quarter of a mile of the Rueben Murrell site.

5.5 Soil

Four soil samples were collected on the Rueben Murrell site. Analysis of these samples showed chemicals associated with the site to be present at levels significantly above background. During the site reconnaissance, two dogs and three kittens were

present on the site and were continuously stepping through the oil and garbage. Two horses graze in the pasture, around the two garbage piles where samples showed contaminated soil.

Mr. and Mrs. Murrell currently reside at the site; their son, Rueben Jr., comes to the site to work on his garbage trucks in the garage. The site is easily accessible from the southern side, where no fencing exists. A barbed wire fence surrounds the entire pasture, but it is in poor condition.

6.0 References

Berg, R.C., and J.P. Kempton, 1988. Stack-unit Mapping of Geological Materials in Illinois to a Depth of 15 Meters. Illinois State Geological Survey, Circular 542.

Decatur, City of, 1992. Telephone conversation between Josephine Ricks, city of Decatur Water Department, and J. Noyes, BVWST, April 1.

Decatur States Attorney Office, 1993. Telephone conversation between Patty, States Attorney Office, and T. Hay, BVWST, March 4.

Illinois Environmental Protection Agency, 1990. "CERCLA Preliminary Assessment Report," Rueben Murrell, Macon County, ILD 984 769 240, March 16.

Illinois Department of Conservation, 1992. Letter to J. Noyes of BVWST from G. Kruse, Project Manager, July 2.

Illinois State Water Survey, 1992. Private Well Data Base, June 25.

Macon County Health Department, 1993. Telephone conversation between Steve Bertesch and T. Hay, BVWST, February 22.

Selkregg, L.F., and J.P. Kempton, 1958. Ground Water Geology in East-Central Illinois. Illinois Geological Survey, Circular 248, 36p.

U.S. Environmental Protection Agency (USEPA), 1988, "Pre-Remedial Strategy for Implementing SARA," Office of Solid Waste and Emergency Response, Washington, D.C., Directive Number 9345.2-101, February 12.

U.S. Environmental Protection Agency (USEPA), 1992a. CERCLIS Site/Event Listing for Illinois, July 8.

USEPA, 1992b. Region V List of RCRA Notifiers in Illinois, July 24.

U.S. Department of Commerce, 1991. Economic and Statistics Administration, Bureau of the Census, "1990 Census of Population and Housing, Summary Population and Housing Characteristics, Illinois," Washington D.C., August.

U.S. Geological Survey, 1982. Topographic map, Harristown, IL, 7.5 minute quadrangle.

Appendix A

Site 4-Mile Radius Map
and
15-Mile Surface Water Route Map

Rueben Murrell

TIC QUADRANGLE
ILLINOIS
E SERIES (TOPOGRAPHIC)
NIANTIC 15' QUADRANGLE
UNITED STATES
RTMENT OF THE INTERIOR
GEOLOGICAL SURVEY
R1E R2E
T 17 N
T 16 N
T 15 N
ILLIOPOLIS
Illiopolis
Niantic
N I A N T I C
M O S Q U I T O
H A R R I S T O W N
Harristown
B L U E M O U N D
DECATUR
Wyckles Corners
ROCK SPRINGS CENTER
SOUTH WHEATLAND
SANGAMON RIVER
Osbernville
Blackland
Boody
LINCOLN TRAIL HOMESTEAD STATE PARK
Millikin University
15 mile downstrean target distance limit is highlighted in yellow
BVWST
N
Site Name: Rueben Murrell
Site ILD: ILD 984 769 240
USGS TOPOGRAPHIC MAPS
Name: Niantic
Date: 1982
Name: Warrensburg
Date: 1982
Name: Harristown
Date: 1982
Name: Decatur
Date: 1975
LEGEND
Municipal Water Boundary
Site Location
Public Well
Private Well
Map Scale
1 ½ 0
Miles



ecology and environment, inc.
SITE NAME MURRELL LANDFILL
U.S. EPA ID# ILD980901540
CONTOUR INTERVAL 5 FEET
USGS TOPOGRAPHIC MAPS:
NAME WARRENSBURG
DATE 1982
REVISED
NAME HARRISTOWN
DATE 1982
REVISED
NAME DECATUR
DATE 1967
REVISED 1975
NAME
DATE
REVISED
SCALE
0
½
1 MILE
QUADRANGLE LOCATION
ILLINOIS
SITE
WELL LOG 1
WELL LOG 2
WELL LOG 3
WELL LOG 4
WELL LOG 5
WELL LOG 6
WELL LOG 7
WELL LOG 8
HARRISTOWN MUNICIPAL WATER BOUNDARY
DECATUR MUNICIPAL WATER BOUNDARY
Harristown
H A R R I S T O W N
B L U E M O U N D
S O U T H W H E A T L A N D
DECATUR
Wyckles Corners
Willow Branch
SANGAMON RIVER
Spring Creek
Rock Spring
Crum Cem
Oil Wells
Oil Well
Oil Tanks
Sewage Disposal Ponds
Drill Hole
Wells
Bethel Academy
Union Chapel
Radio Tower
LINCOLN TRAIL HOMESTEAD STATE PARK
Whitley Cem
Boat Ramp
Gravel Pit
GRAVEL PITS
Muirheid Cem
Brown Cem
Hudelson Cem
Bethlehem Ch
Salem Ch
Bulldog Crossing
Radio Tower (WDZ)
SEWAGE DISPOSAL
ROCK SPRINGS CENTER
FAIRVIEW PARK
GARMAN PARK
GRACELAND CEMETERY
Sanders Park
Franklin Sch
Oak Grove
East Park Academy
Boody
Zion Chapel
Zion Cem
Elwin
OIL FIELD
NORFOLK AND WESTERN
ILLINOIS TERMINAL
BALTIMORE AND OHIO
ILLINOIS CENTRAL
PIPELINES
SPRINGFIELD (INTERSTATE 55) 27 MI.
ILIOPOLIS 7 MI.
BLUE MOUND 4.7 MI.
TAYLORVILLE 19 MI.
(MACON WEST)
MACON 2.8 MI.
280 000 FEET
1 170 000 FEET
T 17 N
T 16 N
T 15 N
R 1 E
R 2 E

Appendix B

USEPA Form 2070-13

Rueben Murrell

POTENTIAL HAZARDOUS WASTE SITE
SITE INSPECTION REPORT
PART 1 - SITE LOCATION AND INSPECTION INFORMATION

I. IDENTIFICATION

01 STATE	02 SITE NUMBER
ILD	954 769 240

II. SITE NAME AND LOCATION

01 SITE NAME (Legal, common, or descriptive name of site)	02 STREET, ROUTE NO., OR SPECIFIC LOCATION IDENTIFIER
Rueben Murrell	Box 153 - Hill Rd.

03 CITY	04 STATE	05 ZIP CODE	06 COUNTY	07 COUNTY CODE	08 CONG DIST
Decatur	IL	62522	Macon	115	20

09 COORDINATES LATITUDE	LONGITUDE
39.79 00.0	088 53 00.0

10 TYPE OF OWNERSHIP (Check one)
☒ A. PRIVATE ☐ B. FEDERAL _____ ☐ C. STATE ☐ D. COUNTY ☐ E. MUNICIPAL
☐ F. OTHER _____ ☐ G. UNKNOWN

III. INSPECTION INFORMATION

01 DATE OF INSPECTION	02 SITE STATUS	03 YEARS OF OPERATION
11 8 92 (MONTH DAY YEAR)	☒ ACTIVE ☐ INACTIVE	1977 (BEGINNING YEAR) present (ENDING YEAR) ___ UNKNOWN

04 AGENCY PERFORMING INSPECTION (Check all that apply)
☐ A. EPA ☒ B. EPA CONTRACTOR BVWST (Name of firm) ☐ C. MUNICIPAL ☐ D. MUNICIPAL CONTRACTOR _____ (Name of firm)
☐ E. STATE ☐ F. STATE CONTRACTOR _____ (Name of firm) ☐ G. OTHER _____ (Specify)

05 CHIEF INSPECTOR	06 TITLE	07 ORGANIZATION	08 TELEPHONE NO.
Mona Reints	Biologist	BVWST	(312) 346-3775
09 OTHER INSPECTORS	10 TITLE	11 ORGANIZATION	12 TELEPHONE NO.
Joe Gadomski	Chemist	BVWST	(312) 346-3775
John Quinn	Geologist	BVWST	(312) 346-3775
Pete Wolsko	Civil Engineer	BVWST	(312) 346-3775
			( )
			( )

13 SITE REPRESENTATIVES INTERVIEWED	14 TITLE	15 ADDRESS	16 TELEPHONE NO
			( )
			( )
			( )
			( )
			( )
			( )

17 ACCESS GAINED BY (Check one)	18 TIME OF INSPECTION	19 WEATHER CONDITIONS
☒ PERMISSION ☐ WARRANT		Light rain. Wind ESE 10-15 mph

IV. INFORMATION AVAILABLE FROM

01 CONTACT	02 OF (Agency/Organization)	03 TELEPHONE NO.
Rueben Murrell	Rueben Murrell	(217) 963-2469

04 PERSON RESPONSIBLE FOR SITE INSPECTION FORM	05 AGENCY	06 ORGANIZATION	07 TELEPHONE NO.	08 DATE
Tonya Hay	EPA CONTRACTOR	BVWST	(312) 346-3775	11 4 92 (MONTH DAY YEAR)

EPA FORM 2070-13 (7-81)

EPA

POTENTIAL HAZARDOUS WASTE SITE
SITE INSPECTION REPORT
PART 2 - WASTE INFORMATION

I. IDENTIFICATION

01 STATE	02 SITE NUMBER
ILD	984-769-240

II. WASTE STATES, QUANTITIES, AND CHARACTERISTICS

01 PHYSICAL STATES (Check all that apply)

- [X] A. SOLID
- [ ] B. POWDER, FINES
- [ ] C. SLUDGE
- [ ] D. OTHER (Specify)
- [ ] E. SLURRY
- [X] F. LIQUID
- [ ] G. GAS

02 WASTE QUANTITY AT SITE

Measures of waste quantities must be independent

TONS: _____

CUBIC YARDS: unknown

NO. OF DRUMS: _____

03 WASTE CHARACTERISTICS (Check all that apply)

- [X] A. TOXIC
- [ ] B. CORROSIVE
- [ ] C. RADIOACTIVE
- [X] D. PERSISTENT
- [ ] E. SOLUBLE
- [ ] F. INFECTIOUS
- [ ] G. FLAMMABLE
- [ ] H. IGNITABLE
- [ ] I. HIGHLY VOLATILE
- [ ] J. EXPLOSIVE
- [ ] K. REACTIVE
- [ ] L. INCOMPATIBLE
- [ ] M. NOT APPLICABLE

III. WASTE TYPE

CATEGORY	SUBSTANCE NAME	01 GROSS AMOUNT	02 UNIT OF MEASURE	03 COMMENTS
SLU	SLUDGE			
OLW	OILY WASTE X	unknown		
SOL	SOLVENTS			
PSD	PESTICIDES			
OCC	OTHER ORGANIC CHEMICALS			
IOC	INORGANIC CHEMICALS			
ACD	ACIDS			
BAS	BASES			
MES	HEAVY METALS			

IV. HAZARDOUS SUBSTANCES (See Appendix for most frequently cited CAS Numbers)

01 CATEGORY	02 SUBSTANCE NAME	03 CAS NUMBER	04 STORAGE/DISPOSAL METHOD	05 CONCENTRATION	06 MEASURE OF CONCENTRATION
	Butylbenzylphthalate		OD	1100	ug/kg
	Chrysene		OD	650	
	Fluoranthene	206-44-0	OD	1400	
	4-Methylphenol			1700	
	2-Methylnaphthalene			710	
	bis(2Ethylhexyl)phthalate			1,4800	
	Benzo(b) Fluoranthene			610	
	Napthalene	91-20-3		530	
	Phenanthrene	85-01-8		1400	
	Pyrene			1200	ug/kg
IOC	Beryllium	7440-41-7		0.77	mg/kg
IOC	Cadmium	7440-43-9		2.0	mg/kg
IOC	Cyanide			0.69	mg/kg
MES	Lead			173	mg/kg
PSD	Aroclor 1242, 1248, 1254			varies	ug/kg
PSD	Gamma Chlordane		OD	11	ug/kg

V. FEEDSTOCKS (See Appendix for CAS Numbers)

CATEGORY	01 FEEDSTOCK NAME	02 CAS NUMBER	CATEGORY	01 FEEDSTOCK NAME	02 CAS NUMBER
FDS			FDS		
FDS			FDS		
FDS			FDS		
FDS			FDS		

VI. SOURCES OF INFORMATION (Cite specific references, e.g., state files, sample analysis, reports)

SSI draft report for Rueben Nurrell

IEPA Preliminary Assessment

EPA FORM 2070-13 (7-81)

EPA

POTENTIAL HAZARDOUS WASTE SITE
SITE INSPECTION REPORT
PART 3 - DESCRIPTION OF HAZARDOUS CONDITIONS AND INCIDENTS

I. IDENTIFICATION
01 STATE: ILD | 02 SITE NUMBER: 984 769 240

II. HAZARDOUS CONDITIONS AND INCIDENTS

01 ☒ A. GROUNDWATER CONTAMINATION
03 POPULATION POTENTIALLY AFFECTED: 720
02 ☐ OBSERVED (DATE: _____) ☒ POTENTIAL ☐ ALLEGED
04 NARRATIVE DESCRIPTION
The rural community on the west side of Decatur, in the vicinity of the Nuttell property; relies on private wells as their primary source of drinking water

01 ☒ B. SURFACE WATER CONTAMINATION
03 POPULATION POTENTIALLY AFFECTED: _____
02 ☐ OBSERVED (DATE: _____) ☒ POTENTIAL ☐ ALLEGED
04 NARRATIVE DESCRIPTION
The Sangamon river is located 900 ft South of the site. the river is used for recreational purposes such as fishing and boating.

01 ☐ C. CONTAMINATION OF AIR
03 POPULATION POTENTIALLY AFFECTED: _____
02 ☐ OBSERVED (DATE: _____) ☐ POTENTIAL ☐ ALLEGED
04 NARRATIVE DESCRIPTION
unk

01 ☐ D. FIRE/EXPLOSIVE CONDITIONS
03 POPULATION POTENTIALLY AFFECTED: _____
02 ☐ OBSERVED (DATE: _____) ☐ POTENTIAL ☐ ALLEGED
04 NARRATIVE DESCRIPTION
unk

01 ☒ E. DIRECT CONTACT
03 POPULATION POTENTIALLY AFFECTED: _____
02 ☐ OBSERVED (DATE: _____) ☐ POTENTIAL ☐ ALLEGED
04 NARRATIVE DESCRIPTION
The property is accessible from the southern side along Hillroad, where no fencing exists and the driveway extends and contaminated soil is found (near garage). A barbed wire fence surrounds the pasture yet it is bordered by woodlands & residences to the east and west.

01 ☒ F. CONTAMINATION OF SOIL
03 AREA POTENTIALLY AFFECTED: _____ (Acres)
02 ☐ OBSERVED (DATE. _____) ☐ POTENTIAL ☐ ALLEGED
04 NARRATIVE DESCRIPTION
The SSI sampling results confirm contamination of soil at the two garage piles and the area south of the garage.

01 ☒ G. DRINKING WATER CONTAMINATION
03 POPULATION POTENTIALLY AFFECTED: 720
02 ☐ OBSERVED (DATE: _____) ☐ POTENTIAL ☐ ALLEGED
04 NARRATIVE DESCRIPTION
See "A" above.

01 ☐ H. WORKER EXPOSURE/INJURY
03 WORKERS POTENTIALLY AFFECTED: _____
02 ☐ OBSERVED (DATE: _____) ☐ POTENTIAL ☐ ALLEGED
04 NARRATIVE DESCRIPTION
unk.

01 ☒ I. POPULATION EXPOSURE/INJURY
03 POPULATION POTENTIALLY AFFECTED: 720
02 ☐ OBSERVED (DATE: _____) ☐ POTENTIAL ☐ ALLEGED
04 NARRATIVE DESCRIPTION
the rural population on the west side of Decatur is approximately 720.

EPA

POTENTIAL HAZARDOUS WASTE SITE
SITE INSPECTION
PART 4 - PERMIT AND DESCRIPTIVE INFORMATION

I. IDENTIFICATION

01 STATE	02 SITE NUMBER
ID	984 769 240

II. PERMIT INFORMATION

01 TYPE OF PERMIT ISSUED (Check all that apply)	02 PERMIT NUMBER	03 DATE ISSUED	04 EXPIRATION DATE	05 COMMENTS
☐ A. NPDES				
☐ B. UIC				
☐ C. AIR				
☐ D. RCRA				
☐ E. RCRA INTERIM STATUS				
☐ F. SPCC PLAN				
☐ G. STATE (Specify)				
☐ H. LOCAL (Specify)				
☐ I. OTHER (Specify)				
☐ J. NONE				

III. SITE DESCRIPTION

01 STORAGE/DISPOSAL (Check all that apply)	02 AMOUNT	03 UNIT OF MEASURE
☐ A. SURFACE IMPOUNDMENT		
☒ B. PILES	unk	
☐ C. DRUMS, ABOVE GROUND		
☐ D. TANK, ABOVE GROUND		
☐ E. TANK, BELOW GROUND		
☐ F. LANDFILL		
☐ G. LANDFARM		
☒ H. OPEN DUMP	unk	
☐ I. OTHER (Specify)		

04 TREATMENT (Check all that apply)

- ☐ A. INCENERATION
- ☐ B. UNDERGROUND INJECTION
- ☐ C. CHEMICAL/PHYSICAL
- ☐ D. BIOLOGICAL
- ☐ E. WASTE OIL PROCESSING
- ☐ F. SOLVENT RECOVERY
- ☐ G. OTHER RECYCLING/RECOVERY
- ☐ H. OTHER (Specify)

05 OTHER

- ☒ A. BUILDINGS ON SITE

06 AREA OF SITE

17 (Acres)

07 COMMENTS

IV. CONTAINMENT

01 CONTAINMENT OF WASTES (Check one)

☐ A. ADEQUATE, SECURE ☐ B. MODERATE ☒ C. INADEQUATE, POOR ☐ D. INSECURE, UNSOUND, DANGEROUS

02 DESCRIPTION OF DRUMS, DIKING, LINERS, BARRIERS, ETC.

The property is easily accessible from the south along Hillroad, where no fencing exists and the driveway extends. A barbed wire fence surrounds the pasture but it is in poor condition and does not restrict access from the north, west and east.

V. ACCESSIBILITY

01 WASTE EASILY ACCESSIBLE: ☒ YES ☐ NO

02 COMMENTS

Oil spillage is all around the driveway and the south side of the garage. Garbage and piles are spread around the pasture

VI. SOURCES OF INFORMATION (Cite specific references, e.g. state files, sample analysis, reports)

SSI Draft Report for Ruben Murrell

EPA

POTENTIAL HAZARDOUS WASTE SITE
SITE INSPECTION REPORT
PART 5 - WATER, DEMOGRAPHIC, AND ENVIRONMENTAL DATA

I. IDENTIFICATION

01 STATE	02 SITE NUMBER
ILD	984 769 240

II. DRINKING WATER SUPPLY

01 TYPE OF DRINKING SUPPLY *(Check as applicable)*

	SURFACE	WELL
COMMUNITY	A. ☒	B. ☐
NON-COMMUNITY	C. ☒	D. ☒

02 STATUS

	ENDANGERED	AFFECTED	MONITORED
COMMUNITY	A. ☐	B. ☐	C. ☐
NON-COMMUNITY	D. ☐	E. ☐	F. ☐

03 DISTANCE TO SITE

A. 5 (mi)
B. > 1/4 (mi)

III. GROUNDWATER

01 GROUNDWATER USE IN VICINITY *(Check one)*

☐ A. ONLY SOURCE FOR DRINKING
☒ B. DRINKING *(Other sources available)* COMMERCIAL, INDUSTRIAL, IRRIGATION *(No other water sources available)*
☐ C. COMMERCIAL, INDUSTRIAL, IRRIGATION *(Limited other sources available)*
☐ D. NOT USED, UNUSEABLE

02 POPULATION SERVED BY GROUND WATER 992

03 DISTANCE TO NEAREST DRINKING WATER WELL > 1/4 (mi)

04 DEPTH TO GROUNDWATER 30 (ft)

05 DIRECTION OF GROUNDWATER FLOW ______

06 DEPTH TO AQUIFER OF CONCERN 30 (ft)

07 POTENTIAL YIELD OF AQUIFER ______ (gpd)

08 SOLE SOURCE AQUIFER ☐ YES ☐ NO

09 DESCRIPTION OF WELLS *(Including useage, depth, and location relative to population and buildings)*

10 RECHARGE AREA ☐ YES ☐ NO COMMENTS

11 DISCHARGE AREA ☐ YES ☐ NO COMMENTS

IV. SURFACE WATER

01 SURFACE WATER USE *(Check one)*

☒ A. RESERVOIR, RECREATION DRINKING WATER SOURCE
☐ B. IRRIGATION, ECONOMICALLY IMPORTANT RESOURCES
☐ C. COMMERCIAL, INDUSTRIAL
☐ D. NOT CURRENTLY USED

02 AFFECTED/POTENTIALLY AFFECTED BODIES OF WATER

NAME:	AFFECTED	DISTANCE TO SITE
Sangamon River	☐	3/8 (mi)
	☐	(mi)
	☐	(mi)

V. DEMOGRAPHIC AND PROPERTY INFORMATION

01 TOTAL POPULATION WITHIN 992 people within 4 miles

ONE (1) MILE OF SITE	TWO (2) MILES OF SITE	THREE (3) MILES OF SITE
A. 224 NO. OF PERSONS	B. ______ NO. OF PERSONS	C. ______ NO. OF PERSONS

02 DISTANCE TO NEAREST POPULATION 4 (mi) (City of Decatur)

03 NUMBER OF BUILDINGS WITHIN TWO (2) MILES OF SITE ______

04 DISTANCE TO NEAREST OFF-SITE BUILDING ______ (mi)

05 POPULATION WITHIN VICINITY OF SITE *(Provide narrative description of nature of population within vicinity of site, e.g., rural, village, densely populated urban area)*

There are two people onsite. 26 people are are within a 1/4 mile with 400 people being within 4 miles.

EPA

POTENTIAL HAZARDOUS WASTE SITE
SITE INSPECTION REPORT
PART 5 - WATER, DEMOGRAPHIC, AND ENVIRONMENTAL DATA

I. IDENTIFICATION

01 STATE: ILD | 02 SITE NUMBER: 984-769-24

VI. ENVIRONMENTAL INFORMATION

01 PERMEABILITY OF UNSATURATED ZONE (Check one)

☐ A. $10^{-6} - 10^{-8}$ cm/sec ☐ B. $10^{-4} - 10^{-6}$ cm/sec ☐ C. $10^{-4} - 10^{-3}$ cm/sec ☐ D. GREATER THAN 10^{-3} cm/sec

02 PERMEABILITY OF BEDROCK (Check one)

☐ A. IMPERMEABLE (Less than 10^{-6} cm/sec) ☒ B. RELATIVELY IMPERMEABLE ($10^{-4} - 10^{-6}$ cm/sec) ☐ C. RELATIVELY PERMEABLE ($10^{-2} - 10^{-4}$ cm/sec) ☐ D. VERY PERMEABLE (Greater than 10^{-2} cm/sec)

03 DEPTH TO BEDROCK	04 DEPTH OF CONTAMINATED SOIL ZONE	05 SOIL pH	
_____ (ft)	sampled to 1/2 (ft)	_____	

06 NET PRECIPITATION	07 ONE YEAR 24 HOUR RAINFALL	08 SLOPE		
		SITE SLOPE	DIRECTION OF SITE SLOPE	TERRAIN AVERAGE SLOPE
_____ (in)	_____ (in)	_____ %		_____ %

09 FLOOD POTENTIAL

SITE IS IN _____ YEAR FLOODPLAIN

10

☐ SITE IS ON BARRIER ISLAND, COASTAL HIGH HAZARD AREA, RIVERINE FLOODWAY

11 DISTANCE TO WETLANDS (5 acre minimum)

ESTUARINE: A. _____ (mi)

OTHER: B. _____ (mi)

12 DISTANCE TO CRITICAL HABITAT (of endangered species)

_____ (mi)

ENDANGERED SPECIES: _____

13 LAND USE IN VICINITY

DISTANCE TO:

COMMERCIAL/INDUSTRIAL	RESIDENTIAL AREAS; NATIONAL/STATE PARKS, FORESTS, OR WILDLIFE RESERVES	AGRICULTURAL LANDS: PRIME AG LAND	AGRICULTURAL LANDS: AG LAND
A. _____ (mi)	B. > 1/4 (mi)	C. _____ (mi)	D. _____ (mi)

14 DESCRIPTION OF SITE IN RELATION TO SURROUNDING TOPOGRAPHY

The Rueben Nurrell site is in a rural area outside of Decatur, Illinois. The property is bordered on the east and west by residential homes, on the south by Hill Road and more residences, and on the north by farmland. Access to the site is gained by a driveway off of Hill road.

Site topography is generally flat except for the southern part of the property which slopes downward Hill road. Surface water runoff is towards the Sangamon River, which is 900 ft south of the site

VII. SOURCES OF INFORMATION (Cite specific references, e.g., state files, sample analysis, reports)

SSI draft report for Rueben Nurrell
PRE score for Rueben Nurrell

EPA

POTENTIAL HAZARDOUS WASTE SITE
SITE INSPECTION REPORT
PART 6 - SAMPLE AND FIELD INFORMATION

I. IDENTIFICATION	
01 STATE	02 SITE NUMBER
LD	984-769-240

II. SAMPLES TAKEN

SAMPLE TYPE	01 NUMBER OF SAMPLES TAKEN	02 SAMPLES SENT TO	03 ESTIMATED DATE RESULTS AVAILABLE
GROUNDWATER			
SURFACE WATER			
WASTE			
AIR			
RUNOFF			
SPILL			
SOIL	4	Wadsworth/alert Laboratories, Inc (organics)	
VEGETATION		IT Analytical Services - Export (inorganics)	
OTHER			

III. FIELD MEASUREMENTS TAKEN

01 TYPE	02 COMMENTS
HCN meter	no readings (0)
RAD Meter	no readings. (0)
HNO	less than 1 ppm

IV. PHOTOGRAPHS AND MAPS

01 TYPE ☒ GROUND ☐ AERIAL

02 IN CUSTODY OF BVWST
*Name of organization or individual

03 MAPS ☐ YES ☐ NO

04 LOCATION OF MAPS

V. OTHER FIELD DATA COLLECTED (Provide narrative description)

VI. SOURCES OF INFORMATION (Cite specific references, e.g., state files, sample analysis, reports)

SSI sampling teams logbook (1/92)

EPA FORM 2070-13 (7-81)

EPA

POTENTIAL HAZARDOUS WASTE SITE
SITE INSPECTION REPORT
PART 7 - OWNER INFORMATION

I. IDENTIFICATION

01 STATE	02 SITE NUMBER
ILD	984 769-240

II. CURRENT OWNER(S)

01 NAME	02 D+B NUMBER
Mr. & Mrs. Rueben Murrell	
03 STREET ADDRESS (P.O. Box, RFD #, etc.)	**04 SIC CODE**
Box 153 Hill Rd	
05 CITY	**06 STATE** / **07 ZIP CODE**
Decatur	IL 62522
01 NAME	**02 D+B NUMBER**
03 STREET ADDRESS (P.O. Box, RFD #, etc.)	**04 SIC CODE**
05 CITY	**06 STATE** / **07 ZIP CODE**
01 NAME	**02 D+B NUMBER**
03 STREET ADDRESS (P.O. Box, RFD #, etc.)	**04 SIC CODE**
05 CITY	**06 STATE** / **07 ZIP CODE**
01 NAME	**02 D+B NUMBER**
03 STREET ADDRESS (P.O. Box, RFD #, etc.)	**04 SIC CODE**
05 CITY	**06 STATE** / **07 ZIP CODE**

PARENT COMPANY (If applicable)

08 NAME	09 D+B NUMBER
10 STREET ADDRESS (P.O. Box, RFD #, etc.)	**11 SIC CODE**
12 CITY	**13 STATE** / **14 ZIP CODE**
08 NAME	**09 D+B NUMBER**
10 STREET ADDRESS (P.O. Box, RFD #, etc.)	**11 SIC CODE**
12 CITY	**13 STATE** / **14 ZIP CODE**
08 NAME	**09 D+B NUMBER**
10 STREET ADDRESS (P.O. Box, RFD #, etc.)	**11 SIC CODE**
12 CITY	**13 STATE** / **14 ZIP CODE**
08 NAME	**09 D+B NUMBER**
10 STREET ADDRESS (P.O. Box, RFD #, etc.)	**11 SIC CODE**
12 CITY	**13 STATE** / **14 ZIP CODE**

III. PREVIOUS OWNER(S) (List most recent first)

01 NAME	02 D+B NUMBER
unknown	
03 STREET ADDRESS (P.O. Box, RFD #, etc.)	**04 SIC CODE**
05 CITY	**06 STATE** / **07 ZIP CODE**
01 NAME	**02 D+B NUMBER**
03 STREET ADDRESS (P.O. Box, RFD #, etc.)	**04 SIC CODE**
05 CITY	**06 STATE** / **07 ZIP CODE**
01 NAME	**02 D+B NUMBER**
03 STREET ADDRESS (P.O. Box, RFD #, etc.)	**04 SIC CODE**
05 CITY	**06 STATE** / **07 ZIP CODE**

IV. REALTY OWNER(S) (If applicable; list most recent first)

01 NAME	02 D+B NUMBER
03 STREET ADDRESS (P.O. Box, RFD #, etc.)	**04 SIC CODE**
05 CITY	**06 STATE** / **07 ZIP CODE**
01 NAME	**02 D+B NUMBER**
03 STREET ADDRESS (P.O. Box, RFD #, etc.)	**04 SIC CODE**
05 CITY	**06 STATE** / **07 ZIP CODE**
01 NAME	**02 D+B NUMBER**
03 STREET ADDRESS (P.O. Box, RFD #, etc.)	**04 SIC CODE**
05 CITY	**06 STATE** / **07 ZIP CODE**

V. SOURCES OF INFORMATION (Cite specific references, e.g., state files, sample analysis, reports)

EPA

POTENTIAL HAZARDOUS WASTE SITE
SITE INSPECTION REPORT
PART 8 - OPERATOR INFORMATION

I. IDENTIFICATION	
01 STATE	02 SITE NUMBER
LD	984-769-240

II. CURRENT OPERATOR (Provide if different from owner)

01 NAME	02 D+B NUMBER	03 STREET ADDRESS (P.O. Box, RFD #, etc.)	04 SIC CODE	05 CITY	06 STATE	07 ZIP CODE	08 YEARS OF OPERATION	09 NAME OF OWNER

OPERATOR'S PARENT COMPANY (If applicable)

10 NAME	11 D+B NUMBER	12 STREET ADDRESS (P.O. Box, RFD #, etc.)	13 SIC CODE	14 CITY	15 STATE	16 ZIP CODE

III. PREVIOUS OPERATOR(S) (List most recent first; provide only if different from owner)

01 NAME	02 D+B NUMBER	03 STREET ADDRESS (P.O. Box, RFD #, etc.)	04 SIC CODE	05 CITY	06 STATE	07 ZIP CODE	08 YEARS OF OPERATION	09 NAME OF OWNER DURING THIS PERIOD

PREVIOUS OPERATORS' PARENT COMPANIES (If applicable)

10 NAME	11 D+B NUMBER	12 STREET ADDRESS (P.O. Box, RFD #, etc.)	13 SIC CODE	14 CITY	15 STATE	16 ZIP CODE

IV. SOURCES OF INFORMATION (Cite specific references, e.g., state files, sample analysis, reports)

EPA FORM 2070-13 (7-81)

EPA

POTENTIAL HAZARDOUS WASTE SITE
SITE INSPECTION REPORT
PART 9 - GENERATOR/TRANSPORTER INFORMATION

I. IDENTIFICATION	
01 STATE	02 SITE NUMBER
ILD	984-769-240

II. ON-SITE GENERATOR

01 NAME	02 D+B NUMBER
03 STREET ADDRESS (P.O. Box, RFD #, etc.)	04 SIC CODE
05 CITY	06 STATE / 07 ZIP CODE

III. OFF-SITE GENERATOR(S)

01 NAME	02 D+B NUMBER	01 NAME	02 D+B NUMBER
03 STREET ADDRESS (P.O. Box, RFD #, etc.)	04 SIC CODE	03 STREET ADDRESS (P.O. Box, RFD #, etc.)	04 SIC CODE
05 CITY	06 STATE / 07 ZIP CODE	05 CITY	06 STATE / 07 ZIP CODE
01 NAME	02 D+B NUMBER	01 NAME	02 D+B NUMBER
03 STREET ADDRESS (P.O. Box, RFD #, etc.)	04 SIC CODE	03 STREET ADDRESS (P.O. Box, RFD #, etc.)	04 SIC CODE
05 CITY	06 STATE / 07 ZIP CODE	05 CITY	06 STATE / 07 ZIP CODE

IV. TRANSPORTER(S)

01 NAME	02 D+B NUMBER	01 NAME	02 D+B NUMBER
03 STREET ADDRESS (P.O. Box, RFD #, etc.)	04 SIC CODE	03 STREET ADDRESS (P.O. Box, RFD #, etc.)	04 SIC CODE
05 CITY	06 STATE / 07 ZIP CODE	05 CITY	06 STATE / 07 ZIP CODE
01 NAME	02 D+B NUMBER	01 NAME	02 D+B NUMBER
03 STREET ADDRESS (P.O. Box, RFD #, etc.)	04 SIC CODE	03 STREET ADDRESS (P.O. Box, RFD #, etc.)	04 SIC CODE
05 CITY	06 STATE / 07 ZIP CODE	05 CITY	06 STATE / 07 ZIP CODE

V. SOURCES OF INFORMATION (Cite specific references, e.g., state files, sample analysis, reports)

EPA

POTENTIAL HAZARDOUS WASTE SITE
SITE INSPECTION REPORT
PART 10 - PAST RESPONSE ACTIVITIES

I. IDENTIFICATION

01 STATE	02 SITE NUMBER
ILD	984-169-240

PAST RESPONSE ACTIVITIES

01 ☐ A. WATER SUPPLY CLOSED — 02 DATE _____ — 03 AGENCY _____
04 DESCRIPTION

01 ☐ B. TEMPORARY WATER SUPPLY PROVIDED — 02 DATE _____ — 03 AGENCY _____
04 DESCRIPTION

01 ☐ C. PERMANENT WATER SUPPLY PROVIDED — 02 DATE _____ — 03 AGENCY _____
04 DESCRIPTION

01 ☐ D. SPILLED MATERIAL REMOVED — 02 DATE _____ — 03 AGENCY _____
04 DESCRIPTION

01 ☐ E. CONTAMINATED SOIL REMOVED — 02 DATE _____ — 03 AGENCY _____
04 DESCRIPTION

01 ☐ F. WASTE REPACKAGED — 02 DATE _____ — 03 AGENCY _____
04 DESCRIPTION

01 ☐ G. WASTE DISPOSED ELSEWHERE — 02 DATE _____ — 03 AGENCY _____
04 DESCRIPTION

01 ☐ H. ON SITE BURIAL — 02 DATE _____ — 03 AGENCY _____
04 DESCRIPTION

01 ☐ I. IN SITU CHEMICAL TREATMENT — 02 DATE _____ — 03 AGENCY _____
04 DESCRIPTION

01 ☐ J. IN SITU BIOLOGICAL TREATMENT — 02 DATE _____ — 03 AGENCY _____
04 DESCRIPTION

01 ☐ K. IN SITU PHYSICAL TREATMENT — 02 DATE _____ — 03 AGENCY _____
04 DESCRIPTION

01 ☐ L. ENCAPSULATION — 02 DATE _____ — 03 AGENCY _____
04 DESCRIPTION

01 ☐ M. EMERGENCY WASTE TREATMENT — 02 DATE _____ — 03 AGENCY _____
04 DESCRIPTION

01 ☐ N. CUTOFF WALLS — 02 DATE _____ — 03 AGENCY _____
04 DESCRIPTION

01 ☐ O. EMERGENCY DIKING/SURFACE WATER DIVERSION — 02 DATE _____ — 03 AGENCY _____
04 DESCRIPTION

01 ☐ P. CUTOFF TRENCHES/SUMP — 02 DATE _____ — 03 AGENCY _____
04 DESCRIPTION

01 ☐ Q. SUBSURFACE CUTOFF WALL — 02 DATE _____ — 03 AGENCY _____
04 DESCRIPTION

EPA

POTENTIAL HAZARDOUS WASTE SITE
SITE INSPECTION REPORT
PART 10 - PAST RESPONSE ACTIVITIES

I. IDENTIFICATION	
01 STATE	02 SITE NUMBER
ILD	984-769-240

II PAST RESPONSE ACTIVITIES (Continued)

01 ☐ R. BARRIER WALLS CONSTRUCTED — 02 DATE _____ — 03 AGENCY _____
04 DESCRIPTION

01 ☐ S. CAPPING/COVERING — 02 DATE _____ — 03 AGENCY _____
04 DESCRIPTION

01 ☐ T. BULK TANKAGE REPAIRED — 02 DATE _____ — 03 AGENCY _____
04 DESCRIPTION

01 ☐ U. GROUT CURTAIN CONSTRUCTED — 02 DATE _____ — 03 AGENCY _____
04 DESCRIPTION

01 ☐ V. BOTTOM SEALED — 02 DATE _____ — 03 AGENCY _____
04 DESCRIPTION

01 ☐ W. GAS CONTROL — 02 DATE _____ — 03 AGENCY _____
04 DESCRIPTION

01 ☐ X. FIRE CONTROL — 02 DATE _____ — 03 AGENCY _____
04 DESCRIPTION

01 ☐ Y. LEACHATE TREATMENT — 02 DATE _____ — 03 AGENCY _____
04 DESCRIPTION

01 ☐ Z. AREA EVACUATED — 02 DATE _____ — 03 AGENCY _____
04 DESCRIPTION

01 ☐ 1. ACCESS TO SITE RESTRICTED — 02 DATE _____ — 03 AGENCY _____
04 DESCRIPTION

01 ☐ 2. POPULATION RELOCATED — 02 DATE _____ — 03 AGENCY _____
04 DESCRIPTION

01 ☐ 3. OTHER REMEDIAL ACTIVITIES — 02 DATE _____ — 03 AGENCY _____
04 DESCRIPTION

III. SOURCES OF INFORMATION (Cite specific references, e.g., state files, sample analysis, reports)

EPA

POTENTIAL HAZARDOUS WASTE SITE
SITE INSPECTION REPORT
PART 10 - PAST RESPONSE ACTIVITIES

I. IDENTIFICATION	
01 STATE	02 SITE NUMBER
ILD	984-764-240

II PAST RESPONSE ACTIVITIES (Continued)

01 ☐ R. BARRIER WALLS CONSTRUCTED — 02 DATE _____ — 03 AGENCY _____
04 DESCRIPTION

01 ☐ S. CAPPING/COVERING — 02 DATE _____ — 03 AGENCY _____
04 DESCRIPTION

01 ☐ T. BULK TANKAGE REPAIRED — 02 DATE _____ — 03 AGENCY _____
04 DESCRIPTION

01 ☐ U. GROUT CURTAIN CONSTRUCTED — 02 DATE _____ — 03 AGENCY _____
04 DESCRIPTION

01 ☐ V. BOTTOM SEALED — 02 DATE _____ — 03 AGENCY _____
04 DESCRIPTION

01 ☐ W. GAS CONTROL — 02 DATE _____ — 03 AGENCY _____
04 DESCRIPTION

01 ☐ X. FIRE CONTROL — 02 DATE _____ — 03 AGENCY _____
04 DESCRIPTION

01 ☐ Y. LEACHATE TREATMENT — 02 DATE _____ — 03 AGENCY _____
04 DESCRIPTION

01 ☐ Z. AREA EVACUATED — 02 DATE _____ — 03 AGENCY _____
04 DESCRIPTION

01 ☐ 1. ACCESS TO SITE RESTRICTED — 02 DATE _____ — 03 AGENCY _____
04 DESCRIPTION

01 ☐ 2. POPULATION RELOCATED — 02 DATE _____ — 03 AGENCY _____
04 DESCRIPTION

01 ☐ 3. OTHER REMEDIAL ACTIVITIES — 02 DATE _____ — 03 AGENCY _____
04 DESCRIPTION

III. SOURCES OF INFORMATION (Cite specific references, e.g., state files, sample analysis, reports)

EPA

POTENTIAL HAZARDOUS WASTE SITE
SITE INSPECTION REPORT
PART 11 - ENFORCEMENT INFORMATION

I. IDENTIFICATION	
01 STATE	02 SITE NUMBER
ILD	984-169-240

II. ENFORCEMENT INFORMATION

01 PAST REGULATORY/ENFORCEMENT ACTION ☒ YES ☐ NO

02 DESCRIPTION OF FEDERAL, STATE, LOCAL REGULATORY/ENFORCEMENT ACTION

A Letter was sent to Mr. Murrell on 3/26/82 by the Macon County Health Department. This letter stated that an inspection was made of his property on 3/23/82, with photos taken. It states that the refuse, bulky wastes, construction and demolition wastes openly dumped on the property are in violation of Article 4, sections 1 and 5 of the Macon County Refuse Ordinance. It stated that the referenced material must either be removed, or covered with two ft. of compacted earth within 30 days or legal action would be instituted.

The outcome of this violation is not known. The Macon Co Health Department has no record of the action taken and the States attorney Office records were destroyed on May 4, 1984.

There are no violations currently pending against the Rubben Murrell site.

III. SOURCES OF INFORMATION (Cite specific references, e.g., state files, sample analysis, reports)

The letter to Mr. Murrell was attached to the IEPA Preliminary Assessment Report.

EPA FORM 2070-13 (7-81)

Appendix C

Target Compound and Analyte Lists

Rueben Murrell

Target Compound List

Volatiles

Chloromethane
Bromomethane
Vinyl Chloride
Chloroethane
Methylene Chloride
Acetone
Carbon Disulfide
1,1-Dichloroethene
1,1-Dichloroethane
1,2-Dichloroethene (total)
Chloroform
1,2-Dichloroethane
2-Butanone
1,1,1-Trichloroethane
Carbon Tetrachloride
Bromodichloromethane
1,2-Dichloropropane
Cis-1,3-Dichloroprpane
Trichloroethene
Dibromochloromethane
1,1,2-Trichloroethane
Benzene
trans-1,3-Dichloropropane
Bromoform
4-Methyl-2-pentanone
2-Hexanone
Tetrachloroethene
Toluene
1,1,2,2-Tetrachloroethane
Chlorobenzene
Ethyl benzene
Styrene
Xylenes (total)

Source: Target Compound List for water and soil with low or medium levels of volatile and semivolatile organic contaminants, as shown in the Quality Assurance Project Plan for Region V Superfund Site Assessment Program, BVWST, September 27, 1991.

Target Compound List (continued)

Semivolatiles

Phenol
bis(2-Chloroethyl) ether
2-Chlorophenol
1,3-Dichlorobenzene
1,4-Dichlorobenzene
1,2-Dichlorobenzene
2-Methylphenol
2,2-oxybis-(1-Chloropropane)*
4-Methylphenol
N-Nitroso-di-n-dipropylamine
Hexachloroethane
Nitrobenzene
Isophorone
2-Nitrophenol
2,4-Dimethylphenol
bis(2-Chloroethoxy) methane
2,4-Dichlorophenol
1,2,4-Trichlorobenzene
Naphthalene
4-Chloroaniline
Hexachlorobutadiene
4-Chloro-3-methylhenol
2-Methylnaphthalene
Hexachlorocyclopentadiene
2,46-Trichlorophenol
2,4,5-Trichlorophenol
2-Chloronephthalene
2-Nitroaniline
Dimethylphthalate
Acenaphthylene
2,6-Dinitrotoluene
3-Nitroaniline
Acenaphthene
2,4-Dinitrophenol
4-Nitrophenol
Dibenzofuran
2,4-Dinitrotoluene
Diethylphthalate
4-Chlorphenyl-phenyl ether
Fluroene
4-Nitroaniline
4,6-Dinitro-2-methylphenol
N-Nitrosodiphenylamine
4-Bromophenyl-phenyl ether
Hexachlorobenzene
Pentachlorophenol
Phenanthrenel
Anthracene
Carbazole
Di-n-butylphthalate
Fluoranthene
Pyrene
Butyl benzyl phthalate
3,3-Dichlorbenzidine
Benzo(a)anthracene
Chrysene
bis(2-Ethylhexyl)phthalate
Di-n-Octyphthalate
Benzo(b)fluoranthene
Benzo(k)fluoranthene
Benzp(a)pyrene
Indeno(1,2,3-cd)pyrene
Dibenzo(a,h)anthracene
Benzo(g,h,i)perylene

*Previously known by the name of bis(2-chlorousipropyl) ether.

Source: Target Compound List for water and soil with low or medium levels of volatile and semivolatile organic contaminants, as shown in the Quality Assurance Project Plan for Region V Superfund Site Assessment Program, BVWST, September 27, 1991.

Target Compound List (continued)

Pesticide/PCB

alpha-BHC	4,4-DDT
beta-BHC	Methoxychlor
delta-BHC	Endrin ketone
gamma-BHC (Lindane)	Endrin aldehyde
Heptachlor	alpha-chlordane
Aldrin	gamma-chlordane
Heptachlor epoxide	Toxaphene
Endosulfan I	Aroclor-1016
Dieldrin	Aroclor-1221
4,4-DDE	Aroclor-1232
Endrin	Aroclor-1242
Endosulfan II	Aroclor-1248
4,4-DDD	Aroclor-1254
Endosulfan sulfate	Aroclor-1260

Source: Target Compound List for water and soil containing less than high concentrations of pesticides/aroclors, as shown in the Quality Assurance Project Plan for Region V Superfund Site Assessment Program, BVWST, September 27, 1991.

Target Analyte List

Aluminum	Magnesium
Antimony	Manganese
Arsenic	Mercury
Barium	Nickel
Beryllium	Potassium
Cadmium	Selenium
Calcium	Silver
Chromium	Sodium
Cobalt	Thallium
Copper	Vanadium
Iron	Zinc
Lead	Cyanide

Source: Target Analyte List in the Quality Assurance Project Plan for Region V Superfund Site Assessment Program, BVWST, September 27, 1991.

Appendix D

Analytical Results

Rueben Murrell

Data Qualifiers		
Analysis	Qualifier	Description
Organic	R	Indicates that the data are unusable. The compound may or may not be present.
	U	Indicates compound was analyzed for but not detected. The associated numerical value is the sample quantitation limit.
	J	Indicates an estimated value. This flag is used either when estimating a concentration for tentatively identified compounds (TICs) where a 1:1 response is assumed, or when the mass spectral data indicate the presence of a compound that meets the identification criteria but the result is less than the sample quantitation limit but greater than zero.
	P	This flag is used for a pesticide/Aroclor target analyte when there is greater than 25% difference for detected concentrations between the two GC columns. The lower of the two values is reported and flagged with a "P".
	B	This flag is sued when the analyte is found in the associated blank as well as in the sample. It indicates possible/probable blank contamination. This flag must be used for a TIC as well as for a positively identified TCL compound.
Inorganic	U	Indicates compound was analyzed for but not detected. The associated numerical value is the sample quantitation limit.
	J	Indicates an estimated value.
	B	Indicates that the reported value is less than the Contract Required Detection Limit (CRDL), but greater than or equal to the Instrument Detection Limit (IDL).
	E	The reported value is estimated because of the presence of interference.
	N	Spiked sample recovery not within control limits.
	S	The reported value was determined by the Method of Standard Additions (MSA).
	W	Post-digestion spike for furnace AA analysis is out of control limits, while sample absorbance is less than 50% of spike absorbance.
	*	Duplicate analysis was not within control limits.

Volatile Organic Anaysis for Soil Rueben Murrell				
Volatile Compound	Sample Location and Number Concentrations in ug/kg			
	SS01	SS02	SS03	SS04
Chloromethane	14UJ	11UJ	15UJ	16UJ
Bromomethane	14U	11U	15U	16U
Vinyl Chloride	14U	11U	15UJ	16UJ
Chloroethane	14U	11U	15U	16U
Methylene Chloride	14U	11U	15U	16U
Acetone	14UJ	20UJ	15U	16U
Carbon Disulfide	14UJ	3J	15U	16UJ
1,1–Dichloroethene	14U	11U	15UJ	16U
1,1–Dichloroethane	14UJ	11UJ	15UJ	16UJ
1,2–Dichloroethene (total)	14U	11U	15U	16U
Chloroform	14U	11U	15U	16U
1,2–Dichloroethane	14U	11U	15U	16U
2–Butanone	14UJ	11UJ	15U	16U
1,1,1–Trichloroethane	14U	11U	15U	16U
Carbon Tetrachloride	14U	11U	15U	16U
Bromodichloromethane	14U	11U	15U	16U
1,2–Dichloropropane	14U	11U	15U	16U
cis–1,3–Dichloropropene	14U	11U	15U	16U
Trichloroethene	14U	11U	15U	16U
Dibromochloromethane	14U	11U	15U	16U
1,1,2–Trichloroethane	14U	11U	15U	16U
Benzene	14U	11U	15U	16U
trans–1,3–Dichloropropene	14U	11U	15U	16U
Bromoform	14U	11U	15U	16U
4–Methyl–2–Pentanone	14UJ	3J	15UJ	16UJ
2–Hexanone	14UJ	11UJ	15UJ	16UJ
Tetrachloroethene	14U	11UJ	15U	16U
1,1,2,2–Tetrachloroethane	14UJ	11UJ	15U	16U
Toluene	14U	3J	12J	5J
Chlorobenzene	14U	11UJ	15U	16U
Ethylbenzene	14U	11UJ	4J	16U
Styrene	14U	11UJ	5J	16U
Xylene (total)	14U	11UJ	15U	16U
Total Number of TICs *	0	3	1	0

NOTE: Number, not concentrations, of tentatively identified compounds (TICs)

Semivolatile Organic Analysis for Soil Rueben Murrell				
	Sample Location and Number Concentrations in ug/kg			
Semivolatile Compound	SS01	SS02	SS03	SS04
Phenol	460 UR	11000 UR	500 UR	530 UR
bis(2–Chloroethyl)Ether	460 U	11000 UR	500 U	530 U
2–Chlorophenol	460 UR	11000 UR	500 UR	530 UR
1,3–Dichlorobenzene	460 U	11000 UR	500 U	530 U
1,4–Dichlorobenzene	460 UR	11000 UR	500 UR	530 UR
1,2–Dichlorobenzene	460 U	11000 UR	500 U	530 U
2–Methylphenol	460 U	11000 UR	500 U	530 U
2,2'–Oxybis(1–Chloropropane)	460 U	11000 UR	500 UJ	530 UJ
4–Methylphenol	460 U	1700 J	500 U	530 U
n–Nitroso–di–n–propylamine	460 UR	11000 UR	500 UR	530 UR
Hexachloroethane	460 U	11000 UR	500 U	530 U
Nitrobenzene	460 U	11000 UR	500 U	530 U
Isophorone	460 U	11000 UR	500 U	530 U
2–Nitrophenol	460 U	11000 UR	500 U	530 U
2,4–Dimethylphenol	460 U	11000 UR	500 U	530 U
bis(2–Chloroethoxy)Methane	460 U	11000 UR	500 U	530 U
2,4–Dichlorophenol	460 U	11000 UR	500 U	530 U
1,2,4–Trichlorobenzene	460 UR	11000 UR	500 UR	530 UR
Naphthalene	460 U	11000 UR	530	530 U
4–Chloroaniline	460 U	11000 UR	500 U	530 U
Hexachlorobutadiene	460 U	11000 UR	500 U	530 U
4–Chloro–3–Methylphenol	460 UR	11000 UR	500 UR	530 UR
2–Methylnaphthalene	460 U	710 J	130 J	530 U
Hexachlorocyclopentadiene	460UJ	11000 UJR	500 UJ	530 UJ
2,4,6–Trichlorophenol	460 U	11000 UR	500 U	530 U
2,4,5–Trichlorophenol	460 U	27000 UR	1200 U	1300 U
2–Chloronaphthalene	460 U	11000 UR	500 U	530 U
2–Nitroaniline	460 U	27000 UR	1200 U	1300 U
Dimethyl Phthalate	460 U	11000 UR	500 U	530 U
Acenaphthylene	460 U	11000 UR	500 U	530 U
2,6–Dinitrotoluene	460 U	11000 UR	500 U	530 U
3–Nitroaniline	460 U	27000 UR	1200 U	1300 U
Acenaphthene	460 UR	11000 UR	500 UR	530 UR

Semivolatile Organic Analysis for Soil Rueben Murrell				
	Sample Location and Number Concentrations in ug/kg			
Semivolatile Compound	SS01	SS02	SS03	SS04
2,4-Dinitrophenol	1100UJ	27000 UJR	1200 UJ	1300 UJ
4-Nitrophenol	1100UJR	27000 UJR	1200 UJR	1300 UJR
Dibenzofuran	460 U	11000 UR	72 J	530 U
2,4-Dinitrotoluene	460 UR	11000 UR	500 UR	530 UR
Diethylphthalate	460 U	11000 UR	500 U	530 U
4-Chlorophenyl Phenyl Ether	460 U	11000 UR	500 U	530 U
Fluorene	460 U	11000 UR	32 J	530 U
4-Nitroaniline	1100U	27000 UJR	1200 UJ	1300 UJ
4,6-Dinitro-2-Methylphenol	1100UJ	27000 UJR	1200 UJ	1300 UJ
n-Nitrosodiphenylamine	460 U	11000 UR	500 U	530 U
4-Bromophenyl Phenyl Ether	460 U	11000 UR	500 U	530 U
Hexachlorobenzene	460 UJ	11000 UJR	500 UJ	530 UJ
Pentachlorophenol	1100UJR	27000 UJR	1200 UJR	1300 UJR
Phenanthrene	460 U	1400 J	300 J	530 U
Anthracene	460 U	11000 UR	41 J	530 U
Carbazole	460 U	11000 UR	500 U	530 U
di-n-Butylphthalate	460 U	11000 UR	500 U	520 JB
Fluoranthene	460 U	1400 J	170 J	37 J
Pyrene	460 UR	1200 J	93 JR	30 JR
Butyl Benzyl Phthalate	460 U	1100 J	90 J	530 U
3,3'-Dichlorobenzidine	460 UJ	11000 UR	500 UJ	530 UJ
Benzo(a)Anthracene	460 U	11000 UR	43 J	530 U
Chrysene	460 U	650 J	100 J	40 J
bis(2-Ethylhexyl)Phthalate	460 UJ	4800 J	1100 J	26 J
di-n-Octyl Phthalate	460 UJ	11000 UJR	500 UJ	530 UJ
Benzo(b)Fluoranthene	460 U	610 J	75 J	43 J
Benzo(k)Fluoranthene	460 U	11000 UR	42 J	530 U
Benzo(a)Pyrene	460 U	11000 UR	34 J	28 J
Indeno(1,2,3-cd)Pyrene	460 U	11000 UR	500 U	530 U
Dibenzo(a,h)Anthracene	460 U	11000 UR	500 U	530 U
Benzo(g,h,i)Perylene	460 U	11000 UR	500 U	530 U
Total Number of TICs*	21	21	21	21

Pesticide and PCB Analysis for Soil Rueben Murrell				
Pesticide / PCB	Sample Location and Number Concentrations in ug/kg			
	SS01	SS02	SS03	SS04
Alpha–BHC	2.4 UJ	17 UJ	2.6 UJ	2.7 U
Beta–BHC	2.4 UJ	17 UJ	2.6 UJ	2.7 U
Delta–BHC	2.4 UJ	17 UJ	2.6 UJ	2.7 U
Gamma–BHC (Lindane)	2.4 UJ	3.1 JP	2.6 UJ	2.7 U
Heptachlor	2.4 R	17 UR	2.6 UR	2.7 UR
Aldrin	2.4 R	17 UR	2.6 UR	2.7 UR
Heptachlor Epoxide	2.4 UJ	17 UJ	2.6 UJ	2.7 U
Endosulfan I	2.4 UJ	17 UJ	2.6 UJ	2.7 U
Dieldrin	4.6 UJ	33 UJ	7.5 JP	5.3 U
4,4'–DDE	4.6 UJ	33 UJ	5.0 UJ	5.3 U
Endrin	4.6 UJ	10 JP	5.0 UJ	5.3 U
Endosulfan II	4.6 UJ	33 UJ	5.0 UJ	5.3 U
4,4'–DDD	4.6 UJ	33 UJ	5.0 UJ	5.3 U
Endosulfan Sulfate	4.6 UJ	33 UJ	5.0 UJ	5.3 U
4,4'–DDT	5.2 JP	24 JP	5.0 UJ	5.3 UJ
Methoxychlor	24 UJ	170 UJ	26 UJ	27 U
Endrin Ketone	4.6 UJ	33 UJ	5.0 UJ	5.3 U
Endrin Aldehyde	4.6 UJ	33 UJ	5.0 UJ	5.3 U
Alpha–Chlordane	2.4 UJ	17 UJ	5.9 JP	2.7 P
Gamma–Chlordane	2.4 UJ	17 UJ	11 JP	2.7 U
Toxaphene	240 UJ	1700 UJ	260 UJ	270 U
Aroclor–1016	46 UJ	330 UJ	50 UJ	53 U
Aroclor–1221	94 UJ	680 UJ	100 UJ	110 U
Aroclor–1232	46 UJ	330 UJ	50 UJ	53 U
Aroclor–1242	46 UJ	330 UJ	510 JP	53 U
Aroclor–1248	46 UJ	810 J	50 UJ	53 U
Aroclor–1254	46 UJ	350 J	50 UJ	150 P
Aroclor–1260	46 UJ	330 UJ	50 UJ	53 U

Inorganic Analysis for Soil Rueben Murrell				
Metals and Cyanide	Sample Locations and Number Concentrations in mg/kg			
	SS01	SS02	SS03	SS04
Aluminum	9230	3650	6300	9360
Antimony	2.3 UJN	1.8 UJN	2.3 UJN	2.6 UJN
Arsenic	4.1	5.6 S	3.0 S	4.5
Barium	99.8	59.7	160	208
Beryllium	0.28 U	0.77 B	0.29 U	0.33 U
Cadmium	0.42 B	2.0	0.96 B	1.6 B
Calcium	2620	117000	6820	5140
Chromium	14.6	9.5	8.5	14.4
Cobalt	10.2 B	4.2 B	8.3 B	10.1 B
Copper	15.9 J*	363 J*	31.4 J*	43.2 J*
Iron	15400 *	17200 *	10600 *	17300 *
Lead	32	126	51	173
Magnesium	2300 *	4200 *	2040 *	2320 *
Manganese	1170	551	1460	1220
Mercury	0.12 U	0.11 U	0.12 U	0.14 U
Nickel	16.9	18.0	12.8	17.2
Potassium	1850 JE	760 BJE	1770 JE	2580 JE
Selenium	0.41 B	0.63 BJW	0.47 B	0.4 B
Silver	0.57 UJN	0.45 UJN	0.59 UJN	0.66 UJN
Sodium	55.5 BJE	252 BJE	160 BJE	69.5 BJE
Thallium	0.54 U	0.45 U	0.59 U	0.66 U
Vanadium	22.7JE	14.3 JE	17.0 JE	23.9 JE
Zinc	65.7J*	239 J*	171 J*	1280 J*
Cyanide	0.28 U	0.23 U	0.66 B	0.49 B

Volatile Organic Analysis for Soil
Tentatively Identified Compounds
Rueben Murrell SSI

Sample SS02		
Compound Name	Retention Time	Estimated Concentration (ug/kg)
Unknown	21.8	11 J
Unknown Alkane	21.6	21 J
Unknown	23.5	26 J
Sample SS03		
Compound Name	Retention Time	Estimated Concentration (ug/kg)
Methyl–cyclohexane	13.73	9 JN

Semivolatile Organic Analysis for Soil
Tentatively Identified Compounds
Rueben Murrell SSI

Sample SS01		
Compound Name	Retention Time	Estimated Concentration (ug/kg)
Aldol Condensation Product	3.4	19000 U
Unknown	5.5	340 J
Ethanol,2-(2-Etheoxyethoxy)-	5.7	220 U
Unknown	6.4	760 J
Unknown Acid	11.6	140 J
Unknown Acid	16.8	200 J
Unknown	21.1	200 J
Unknown	22.5	580 J
Unknown	23.4	240 J
Unknown	23.8	1300 J
Unknown Hydrocarbon	25.0	320 J
Unknown	25.2	320 J
Unknown	25.8	280 J
Unknown	26.0	140 J
Unknown	26.1	130 J
Unknown	26.4	800 J
Unknown	26.5	220 J
Unknown	26.7	400 J
Unknown	26.8	460 J
Unknown	27.0	220 J
Unknown	27.3	360 J

Semivolatile Organic Analysis for Soil
Tentatively Identified Compounds
Rueben Murrell SSI

Sample SS02		
Compound Name	Retention Time	Estimated Concentration
Aldol Condensation Product	3.1	15000 UR
Unknown Hydrocarbon	13.6	8000 J
Unknown Hydrocarbon	14.2	26000 J
Unknown Hydrocarbon	15.2	11000 J
Unknown	19.6	9000 J
Unknown	21.0	11000 J
Unknown Hydrocarbon	21.3	11000 J
Unknown	21.7	9400 J
Unknown Hydrocarbon	22.1	12000 J
Unknown Hydrocarbon	22.6	16000 J
Unknown	22.8	13000 J
Unknown	23.3	10000 J
Unknown	23.5	14000 J
Unknown	24.1	12000 J
Unknown	24.7	15000 J
Unknown	24.8	11000 J
Unknown PolyaeromaticHydrocarbon	25.2	16000 J
Unknown PolyaeromaticHydrocarbon	25.3	15000 J
Unknown PolyaeromaticHydrocarbon	25.9	8800 J
Unknown Hydrocarbon	26.2	8000 J
Unknown Hydrocarbon	26.5	13000 J

Semivolatile Organic Analysis for Soil
Tentatively Identified Compounds
Rueben Murrell SSI

Sample SS03		
Compound Name	Retention Time	Estimated Concentration(ug/kg)
Aldol Condensation Product	3.4	34000 U
Unknown	13.7	560 J
Unknown	14.1	660 J
Unknown	16.1	560 J
Unknown Acid	16.6	520 J
Unknown Acid	16.7	740 J
Unknown	20.6	2200 J
Unknown	20.9	660 J
Unknown	21.0	580 J
Unknown	21.4	1800 J
Unknown	21.7	900 J
Unknown Hydrocarbon	22.4	1200 J
Unknown	24.0	1000 J
Unknown Hydrocarbon	24.3	720 J
Unknown Hydrocarbon	24.9	1800 J
Unknown	25.8	760 J
Unknown	26.0	740 J
Unknown	26.1	1100 J
Unknown	26.2	2200 J
Unknown	26.7	2200 J
Unknown	26.9	840 J

Semivolatile Organic Analysis for Soil
Tentatively Identified Compounds
Rueben Murrell SSI

Sample SS04		
Compound Name	Retention Time	Estimated Concentration(ug/kg)
Aldol Condensation Product	3.3	20000 U
Unknown Hydrocarbon	22.3	240 J
Unknown Hydrocarbon	23.6	1700 J
Unknown	24.8	420 J
Unknown Hydrocarbon	24.8	1400 J
Unknown Hydrocarbon	24.8	340 J
Unknown	25.0	260 J
Unknown	25.7	440 J
Unknown	25.8	640 J
Unknown Hydrocarbon	26.0	580 J
Unknown Hydrocarbon	26.0	380 J
Unknown	26.2	920 J
Unknown	26.3	220 J
Unknown	26.5	560 J
Unknown	26.6	420 J
Unknown	26.6	340 J
Unknown	26.8	780 J
Unknown	27.1	460 J
Unknown	27.4	660 J
Unknown	27.6	380 J
Unknown	27.9	300 J

Appendix E

Photographs

Rueben Murrell


HORSE PASTURE/GRASSLAND
VARIOUS TRASH
10, 11
GARBAGE PILES
8, 9
4
FISH POND
BARBED WIRE FENCING
GATE
MURRELL RESIDENCE
WELL
3 CAR GARAGE
OIL RESIDUE AREA
1
2, 6, 7
3
5
HILL ROAD
SANGAMON RIVER (APPROXIMATELY 900')
Not to Scale
N
PHOTOGRAPH LOCATION MAP
RUEBEN MURRELL
DECATUR, ILLINOIS
B&V Waste Science and Technology Corp.

Date: 9-18-91

Time: N/A

Photo Taken By: J. Quinn

Photo Number: 1

Location/ILD #:
Rueben Murrell
ILD 984 769 240

Direction of Photo: Northeast

Description: Southwestern end of garage, northwest end of driveway. Note oil stained driveway.

Date: 9-18-91

Time: N/A

Photo Taken By: J. Quinn

Photo Number: 2

Location/ILD #:
Rueben Murrell
ILD 984 769 240

Direction of Photo: North

Description: Note oil, mud debris at southeastern edge of garage.

Date: 9-18-91

Time: N/A

Photo Taken By: J. Quinn

Photo Number: 3

Location/ILD #:
Rueben Murrell
ILD 984 769 240

Direction of Photo: Southwest

Description: Note mud and oil areas along southwestern portion of driveway. Dog for scale.

Date: 9-18-91

Time: N/A

Photo Taken By: J. Quinn

Photo Number: 4

Location/ILD #:
Rueben Murrell
ILD 984 769 240

Direction of Photo: West

Description: Area of scattered garbage pile. This is the south trash pile.

Date: 1-8-92

Time: 8:50

Photo Taken By: R. Reints

Photo Number: 5

Location/ILD #:
Rueben Murrell
ILD 984 769 240

Direction of Photo: Northwest

Description: View of sample location SS01 taken south of Murrells residence.

Date: 1-8-92

Time: 8:50

Photo Taken By: R. Reints

Photo Number: 6

Location/ILD #:
Rueben Murrell
ILD 984 769 240

Direction of Photo: Northwest

Description: View of sample location SS02 taken south of garage.

Date: 1-8-92

Time: 8:55

Photo Taken By: R. Reints

Photo Number: 7

Location/ILD #:
Rueben Murrell
ILD 984 769 240

Direction of Photo: Northwest

Description: Expanded view of sample location SS02.

Date: 1-8-92

Time: 9:00

Photo Taken By: R. Reints

Photo Number: 8

Location/ILD #:
Rueben Murrell
ILD 984 769 240

Direction of Photo: South

Description: Sample location SS03 taken from southern trash pile.

Date: 1-8-92

Time: 9:00

Photo Taken By: R. Reints

Photo Number: 9

Location/ILD #:
Rueben Murrell
ILD 984 769 240

Direction of Photo: South

Description: Expanded view of sample location SS03.

Date: 1-8-92

Time: 9:10

Photo Taken By: R. Reints

Photo Number: 10

Location/ILD #:
Rueben Murrell
ILD 984 769 240

Direction of Photo: South

Description: View of sample location SS04 taken from near south trash pile.

Date: 1-8-92

Time: 9:10

Photo Taken By: R. Reints

Photo Number: 11

Location/ILD #:
Rueben Murrell
ILD 984 769 240

Direction of Photo: South

Description: Expanded view of sample location SS04.

Date: 1-8-92

Time: 14:35

Photo Taken By: J. Gadomski

Photo Number: 12

Location/ILD #:
Rueben Murrell
ILD 984 769 240

Direction of Photo: N/A

Description: Photo of cooler prior to packaging and shipment.

Appendix F

Representative Well Logs

Rueben Murrell

REFERENCE NUMBER 004

White Copy – Public Health
Yel. – Well Contractor
Blue – Owner

FILL IN ALL PERTINENT INFORMATION REQUESTED AND MAIL ORIGINAL TO STATE DEPARTMENT OF PUBLIC HEALTH, CONSUMER HEALTH PROTECTION, 535 WEST JEFFERSON, SPRINGFIELD, ILLINOIS, 62761. DO NOT DETACH GEOLOGICAL/WATER SURVEYS SECTION. BE SURE TO PROVIDE PROPER WELL LOCATION.

ILLINOIS DEPARTMENT OF PUBLIC HEALTH
WELL CONSTRUCTION REPORT

1. Type of Well
   a. Dug____. Bored X. Hole Diam. 43 in. Depth 40 ft.
   Curb material _____. Buried Slab: Yes X No____
   b. Driven _____. Drive Pipe Diam. ____in. Depth ____ft.
   c. Drilled _____. Finished in Drift X. In Rock____.
   Tubular _____. Gravel Packed X.
   d. Grout:

(KIND)	FROM (Ft.)	TO (Ft.)

2. Distance to Nearest:
   Building 100 Ft. Seepage Tile Field _____
   Cess Pool _____ Sewer (non Cast iron) _____
   Privy _____ Sewer (Cast iron) _____
   Septic Tank _____ Barnyard _____
   Leaching Pit _____ Manure Pile _____
3. Well furnishes water for human consumption? Yes X No____
4. Date well completed 9-74
5. Permanent Pump Installed? Yes X Date 9-74 No____
   Manufacturer F & W Type Sub Location Well
   Capacity 10 gpm. Depth of Setting 35 Ft.
6. Well Top Sealed? Yes X No____ Type _____
7. Pitless Adapter Installed? Yes X No____
   Manufacturer Beker Model Number 6"
   How attached to casing? Bolt
8. Well Disinfected? Yes X No____
9. Pump and Equipment Disinfected? Yes X No____
10. Pressure Tank Size 82 Gal. Type galv.
    Location Basement
11. Water Sample Submitted? Yes____ No____

REMARKS:

GEOLOGICAL AND WATER SURVEYS WELL RECORD

10. Property owner Non - Responsive Well No. ____
    Address Non - Responsive Non - Responsive
    Driller Leo Coath License No. 102-15
11. Permit No. 84495 Date 9-79
12. Water from Clarksville Formation 13. County Macon
    at depth 17 to 18 ft.
14. Screen: Diam. ____in.
    Length: ____ft. Slot _____
    Sec. 24 b
    Twp. 16N
    Rge. 1E
    Elev. ____



SHOW LOCATION IN SECTION PLAT
NE SE SE

15. Casing and Liner Pipe

Diam. (in.)	Kind and Weight	From (Ft.)	To (Ft.)
6	PVC	0	14
36	Concrete	14	40

16. Size Hole below casing: ____in.
17. Static level ____ft. below casing top which is ____ft. above ground level. Pumping level ____ft. when pumping at ____ gpm for ____ hours.

18. FORMATIONS PASSED THROUGH	THICKNESS	DEPTH OF BOTTOM
Top soil	1	1
Yellow Clay	7	8
Drift	9	17
Sandy Clay	1	18
Drift	22	40

(CONTINUE ON SEPARATE SHEET IF NECESSARY)

SIGNED George E. Coath Jr. DATE 9/79

IDPH 4.065
1/74 – KNB-1

ILLEGIBLE COPY

White Copy – Ill. Dept. of Pub. Health
Yellow Copy – Well Contractor
Blue Copy – Well Owner

INSTRUCTIONS TO DRILLERS

FILL IN ALL PERTINENT INFORMATION REQUESTED AND MAIL ORIGINAL TO STATE DEPARTMENT OF PUBLIC HEALTH, HEALTH PROTECTION, ENVIRONMENTAL HEALTH, 525 WEST JEFFERSON, SPRINGFIELD, ILLINOIS 62761. DO NOT DETACH GEOLOGICAL/WATER SURVEYS SECTION. BE SURE TO PROVIDE PROPER WELL LOCATION.

ILLINOIS DEPARTMENT OF PUBLIC HEALTH WELL CONSTRUCTION REPORT

1. Type of Well
   a. Dug ____. Bored X. Hole Diam. 36 in. Depth 73 ft.
   Curb material Tile. Buried Slab: Yes X No ____
   b. Driven ____. Drive Pipe Diam. ____ in. Depth ____ ft.
   c. Drilled ____. Finished in Drift ____. In Rock ____.
   Tubular ____. Gravel Packed X.
   d. Grout:

(KIND)	FROM (Ft.)	TO (Ft.)

2. Distance to Nearest:
   Building 100 Ft. Seepage Tile Field ____
   Cess Pool ____ Sewer (non Cast iron) ____
   Privy ____ Sewer (Cast iron) ____
   Septic Tank 92 Barnyard ____
   Leaching Pit ____ Manure Pile ____
3. Well furnishes water for human consumption? Yes ____ No ____
4. Date well completed 6-8-88
5. Permanent Pump Installed? Yes ____ Date ____ No ____
   Manufacturer ____ Type ____ Location ____
   Capacity ____ gpm. Depth of Setting ____ Ft.
6. Well Top Sealed? Yes X No ____ Type Buried Slab
7. Pitless Adapter Installed? Yes ____ No ____
   Manufacturer ____ Model Number ____
   How attached to casing? ____
8. Well Disinfected? Yes ____ No X
9. Pump and Equipment Disinfected? Yes ____ No ____
10. Pressure Tank Size ____ gal. Type ____
    Location ____
11. Water Sample Submitted? Yes ____ No X

REMARKS:

Co # 22041

GEOLOGICAL AND WATER SURVEYS WELL RECORD

10. Property owner [redacted] Well No. ____
    Address [redacted]
    Driller [illegible] License No. 004120033[illegible]
11. Permit No. 003146 Date 6-8-88
12. Water from ____ (Formation) 13. County [illegible]
    at depth 28 to 40 ft. Sec. 24 [illegible]
14. Screen: Diam. ____ in. Twp. 16 N
    Length: ____ ft. Slot ____ Rge. 1E
    Elev. ____
15. Casing and Liner Pipe

Diam. (in.)	Kind and Weight	From (Ft.)	To (Ft.)
6	Sch 21	0	10
36		10	73

SHOW LOCATION IN SECTION PLAT: NW NW NE

16. Size Hole below casing: ____ in.
17. Static level ____ ft. below casing top which is ____ ft. above ground level. Pumping level ____ ft. when pumping at ____ gpm for ____ hours.

18. FORMATIONS PASSED THROUGH	THICKNESS	DEPTH OF BOTTOM
Top Soil	4	
Yellow clay	28	
Sand and clay	15	
Gray Silt	26	

(CONTINUE ON SEPARATE SHEET IF NECESSARY)

SIGNED [signature] DATE Aug 9-88

White Copy – Ill. Dept. of Public Health
Yellow Copy – Well Contractor
Blue Copy – Well Owner

INSTRUCTIONS TO [illegible]ERS

FILL IN ALL PERTINENT INFORMATION REQUESTED AND MAIL ORIGINAL TO STATE DEPARTMENT OF PUBLIC HEALTH, CONSUMER HEALTH PROTECTION, 535 WEST JEFFERSON, SPRINGFIELD, ILLINOIS, 62761. DO NOT DETACH GEOLOGICAL/WATER SURVEYS SECTION. BE SURE TO PROVIDE PROPER WELL LOCATION.

ILLINOIS DEPARTMENT OF PUBLIC HEALTH
WELL CONSTRUCTION REPORT

1. Type of Well
   a. Dug ___. Bored ✓. Hole Diam. 44 in. Depth 36 ft.
   Curb material Concrete Buried Slab: Yes ✓ No ___
   b. Driven ___. Drive Pipe Diam. ___ in. Depth ___ ft.
   c. Drilled ___. Finished in Drift ___. In Rock ___.
   Tubular ___. Gravel Packed ___.
   d. Grout:

(KIND)	FROM (Ft.)	TO (Ft.)

2. Distance to Nearest:
   Building ___ Ft. Seepage Tile Field ___
   Cess Pool ___ Sewer (non Cast iron) ___
   Privy ___ Sewer (Cast iron) ___
   Septic Tank ___ Barnyard ___
   Leaching Pit ___ Manure Pile ___
3. Well furnishes water for human consumption? Yes ✓ No ___
4. Date well completed 6-28-85
5. Permanent Pump Installed? Yes ___ Date ___ No ✓
   Manufacturer ___ Type ___ Location ___
   Capacity ___ gpm. Depth of Setting ___ Ft.
6. Well Top Sealed? Yes ✓ No ___ Type ___
7. Pitless Adapter Installed? Yes ___ No ✓
   Manufacturer ___ Model Number ___
   How attached to casing? ___
8. Well Disinfected? Yes ___ No ✓
9. Pump and Equipment Disinfected? Yes ___ No ✓
10. Pressure Tank Size ___ gal. Type ___
    Location ___
11. Water Sample Submitted? Yes ___ No ✓

REMARKS:
New const - County 21866
no bldg yet.

GEOLOGICAL AND WATER SURVEYS WELL RECORD

10. Property owner: Non - Responsive Well No. ___
    Address Non - Responsive
    Driller [illegible] License No. 71-607
11. Permit No. 118454 Date 6-15-85
12. Water from [illegible] Formation 13. County McLean
    at depth 20 to 32 ft.
14. Screen: Diam. ___ in.
    Length: ___ ft. Slot ___
    Sec. 24.6 Twp. 16N Rge. 1E Elev. ___



SHOW LOCATION IN SECTION PLAT
SW NE NW

15. Casing and Liner Pipe

Diam. (In.)	Kind and Weight	From (Ft.)	To (Ft.)
6	plastic		10
36	concrete		36

16. Size Hole below casing: ___ in.
17. Static level ___ ft. below casing top which is ___ ft. above ground level. Pumping level ___ ft. when pumping at ___ gpm for ___ hours.

18. FORMATIONS PASSED THROUGH	THICKNESS	DEPTH OF BOTTOM
Clay		12
gravelly yellow clay		20
gravel & gray clay mix		32
gray clay		36

(CONTINUE ON SEPARATE SHEET IF NECESSARY)

SIGNED [signature] DATE 6-28-85

IL 4.065

White Copy – Ill. Dept. of Public Health
Yellow Copy – Well Contractor
Blue Copy – Well Owner

INSTRUCTION TO DRILLERS

FILL IN ALL PERTINENT INFORMATION REQUESTED AND MAIL ORIGINAL TO STATE DEPARTMENT OF PUBLIC HEALTH, CONSUMER HEALTH PROTECTION, 535 WEST JEFFERSON, SPRINGFIELD, ILLINOIS, 62761. DO NOT DETACH GEOLOGICAL/WATER SURVEYS SECTION. BE SURE TO PROVIDE PROPER WELL LOCATION.

ILLINOIS DEPARTMENT OF PUBLIC HEALTH WELL CONSTRUCTION REPORT

1. Type of Well
   a. Dug ____. Bored ✓. Hole Diam. 44 in. Depth 56 ft.
   Curb material ____. Buried Slab: Yes ____ No ____
   b. Driven ____. Drive Pipe Diam. ____ in. Depth ____ ft.
   c. Drilled ____. Finished in Drift ____. In Rock ____.
   Tubular ____. Gravel Packed ✓.
   d. Grout:

(KIND)	FROM (Ft.)	TO (Ft.)

2. Distance to Nearest:
   Building ____ Ft. Seepage Tile Field ____
   Cess Pool ____ Sewer (non Cast Iron) ____
   Privy ____ Sewer (Cast Iron) ____
   Septic Tank ____ Barnyard ____
   Leaching Pit ____ Manure Pile ____
3. Well furnishes water for human consumption? Yes ____ No ____
4. Date well completed ____
5. Permanent Pump Installed? Yes ____ Date ____ No ____
   Manufacturer ____ Type ____ Location ____
   Capacity ____ gpm. Depth of Setting ____ Ft.
6. Well Top Sealed? Yes ✓ No ____ Type ____
7. Pitless Adapter Installed? Yes ____ No ____
   Manufacturer Baker Model Number ____
   How attached to casing? Clamp [illegible]
8. Well Disinfected? Yes ____ No ____
9. Pump and Equipment Disinfected? Yes ____ No ____
10. Pressure Tank Size ____ gal. Type ____
    Location ____
11. Water Sample Submitted? Yes ____ No ____

REMARKS:

GEOLOGICAL AND WATER SURVEYS WELL RECORD

10. Property owner [redacted] No. ____
    Address [redacted]
    Driller Jack Carpenter [illegible] License No. 92-604
11. Permit No. 73-036 Date 12/22/78
12. Water from Sand & Clay (Formation) 13. County Macon
    at depth 32 to 56 ft. Sec. 24 Twp. 16N Rge. 1E Elev. ____
14. Screen: Diam. ____ in.
    Length: ____ ft. Slot ____
15. Casing and Liner Pipe

Diam. (in.)	Kind and Weight	From (Ft.)	To (Ft.)
12"	Concrete	+1	-44
36"	Cement	+14	56

SHOW LOCATION IN SECTION PLAT: SE SE NW

16. Size Hole below casing: ____ in.
17. Static level ____ ft. below casing top which is ____ ft. above ground level. Pumping level ____ ft. when pumping at ____ gpm for ____ hours.

18. FORMATIONS PASSED THROUGH	THICKNESS	DEPTH OF BOTTOM
Top Soil	0-3'	
Yellow Clay	14'	
[illegible]	23'	
Sand & Clay	32'	
Blue Clay	46'	
Sand-Gravel	49'	
Blue Clay	52'	

(CONTINUE ON SEPARATE SHEET IF NECESSARY)

SIGNED Carl & Reynolds Well Drilling / [illegible] Reynolds / [illegible] DATE 12-26-78

4.065
– KNB-1

White Copy – Ill. Dept. of Public Health
Yellow Copy – Well Contractor
Blue Copy – Well Owner

INSTRUCTIONS TO DRILLERS

FILL IN ALL PERTINENT INFORMATION REQUESTED AND MAIL ORIGINAL TO STATE DEPARTMENT OF PUBLIC HEALTH, CONSUMER HEALTH PROTECTION, 535 WEST JEFFERSON, SPRINGFIELD, ILLINOIS, 62761. DO NOT DETACH GEOLOGICAL/WATER SURVEYS SECTION. BE SURE TO PROVIDE PROPER WELL LOCATION.

ILLINOIS DEPARTMENT OF PUBLIC HEALTH
WELL CONSTRUCTION REPORT

1. Type of Well
   a. Dug____. Bored X. Hole Diam. 44 in. Depth 73 ft.
   Curb material _____. Buried Slab: Yes X No _____
   b. Driven _____. Drive Pipe Diam. _____ in. Depth _____ ft.
   c. Drilled _____. Finished in Drift _____. In Rock _____.
   Tubular _____. Gravel Packed X.
   d. Grout:

(KIND)	FROM (Ft.)	TO (Ft.)

2. Distance to Nearest:
   Building _____ Ft. Seepage Tile Field _____
   Cess Pool _____ Sewer (non Cast iron) _____
   Privy _____ Sewer (Cast iron) _____
   Septic Tank _____ Barnyard _____
   Leaching Pit _____ Manure Pile _____
3. Well furnishes water for human consumption? Yes X No _____
4. Date well completed June 27, 1979
5. Permanent Pump Installed? Yes X Date 7/79 - BY CUSTOMER
   Manufacturer Valley Type ½ HP Location well
   Capacity 12 gpm. Depth of Setting 52 Ft.
6. Well Top Sealed? Yes X No _____ Type _____
7. Pitless Adapter Installed? Yes X No _____
   Manufacturer Baker Model Number _____
   How attached to casing? Clamp
8. Well Disinfected? Yes _____ No _____
9. Pump and Equipment Disinfected? Yes _____ No _____
10. Pressure Tank Size 42 gal. Type Well-x-Trol
    Location house
11. Water Sample Submitted? Yes _____ No _____

REMARKS:

GEOLOGICAL AND WATER SURVEYS WELL RECORD

10. Property owner [redacted] Well [redacted]
    Driller Joseph R. Reynolds License No. 92-601
11. Permit No. 87194 Date June 27, 1979
12. Water from Glacial Drift (Formation) 13. County Macon
    at depth 44 to 60 ft. 73
14. Screen: Diam. _____ In.
    Length: _____ ft. Slot _____
    Sec. 25
    Twp. 16N
    Rge. 1E
    Elev. _____

15. Casing and Liner Pipe

Diam. (In.)	Kind and Weight	From (Ft.)	To (Ft.)
10	Plastic	+1	-17
36	Concrete	-17	-60
44	Concrete	-60	-73

SHOW LOCATION IN SECTION PLAT
NE NW SE

16. Size Hole below casing: _____ In.
17. Static level _____ ft. below casing top which is _____ ft. above ground level. Pumping level _____ ft. when pumping at _____ gpm for _____ hours.

18. FORMATIONS PASSED THROUGH	THICKNESS	DEPTH OF BOTTOM
Top Soil	0-3'	
Hard Pan	20'	
Glacial Drift	38'	
Sand	42'	
Glacial Drift	55'	
Sand	60'	
Sand	73'	

(CONTINUE ON SEPARATE SHEET IF NECESSARY)

SIGNED Joseph R Reynolds DATE June 28, 1979

IDPH 4.065
1/74 – KND-1